



Concrete Roads & Road Solutions (CRRS)

CRRS – Durapatcher

- Easy 4 step process
- Low Maintenance
- Ergonomic No – stress Boom
- Vent Flo Nozzle

○ The Spray Patching Process – The spray patcher removes the pothole in one quick and cost effective 4 step process.

1. Clean the area with compressed air.
2. Apply an emulsion tack coat.
3. Fill the hole with coated aggregate.
4. Cover with dry aggregate so traffic can resume immediately.





Low Maintenance / Hi - Performance

The Durapatcher air- driven system utilizes virtually no moving parts in the delivery system. No augers, conveyors or other wear parts are required making it the most reliable in the industry. Aggregate is gravity fed from the tow vehicle completing the worry- free package . The system will deliver aggregate up to 2.5 inches in diameter without plugging or adjustment.

Ergonomic No- Strees Boom

The 3 piece boom design provides the ultimate in support for the operator moving the delivery hose. The boom / slide system easily moves throughout the entire 18 foot working radius allowing for smooth patching anywhere in the work zone.

Vent-Flo Nozzle

The specially designed Vent-Flo nozzle properly coats the aggregate with the right amount of emulsion regardless of aggregate size. The mix is applied at an angle to the repair allowing maximum placement into the repair.

Heated Emulsion Tank

The emulsion tank provides enough product to apply over 10 tons of patch before refilling . The heating blankets allow the patcher to be plugged in to keep emulsion at a “ready – to – go ” temperature.



Gravity feed delivery



Over night heating system

Other Patching Product :

Dura Truck



Dura Maxx





SPECIFICATIONS	
Emulsion Capacity (US gallons):	250
Aggregate Capacity:	N/A
Engine:	74HP IT4 Diesel
Heating Method (overnight):	Electric Blanket
Heat Rating (watts):	2 x 1500 W
Tank Insulation:	R 15
Blower:	450 CFM at 1500 RPM, 10 PSI
GVWR (lbs):	10,400
GAWR (lbs):	2 x 6000
Axle/Suspension:	2 (leaf spring)
Brake Type:	Electric
Clean Out:	15 gallons
Fuel Capacity:	18 gallons
Trailer Construction:	2" x 6" x 1/4" rectangular tube
Drain Valve:	3 in.
Temperature Gauge:	5 in.
Dimensions (l x w x h):	194" x 96" x 91"
Shipping Weight (lbs):	5,560
Warranty:	Two Year Limited



Dura Tank



Vent-Flo Nozzle with optional heater



Ergonomic No Stress Boom

NEHA INFRA SERVICES



Neha Infra Services

Kindly forward your inquiries to :

NEHA INFRA SERVICES

Add : 5D/10; Gr Flr,Varma Villa Compd,
Vithalbhai Road,Vile Parle(West), Mumbai 400056 .

Email : nehainfraservices@gmail.com

Landline : 022 26704011



Neha Infra Services